

DISTRICT HEATING ACCUMULATOR MANNHEIM / GERMANY

FABRICATION, SUPPLY, ERECTION, COMMISSIONING AND DOCUMENTATION



Client:
GKM Mannheim AG

Construction period:
September 2012 – October 2013

Productivity:
Fabrication, supply, erection, commissioning
and documentation

District heating accumulator

Technical data:

Diameter:	40m
Height:	36m
Volume:	45000m ³
Weight:	1265 t
Material:	P355NH

Engineering & Maintenance

Continental Europe

Bilfinger Industrial Services GmbH
Dieselstraße 2 · 4600 Wels · Austria
Phone +43 7242 406-311
christian.hofer@bilfinger.com · www.bis-austria.bilfinger.com



BILFINGER